KOLAR DIVISION.

Dated 6th August 1912.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 24th August 1912, for constructing quarters for the Sub-Assistant Surgeon and the midwife at Bagepalli. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1913.

2. The plans, detailed estimate, specification and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing quarters for the Sub-Assistant Surgeon and Midwife at Bagepalli," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be equired to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items of work.	*Per*	*Quantity.*
Quarters for the Hospital Assistant.		
Earthwork excavation	C. yd.	70
Concrete foundation (bedding)	C. ft.	90
Stone in mud (foundation)	,,	977
Burnt brick in mortar	,,	539
Burnt stone in chunam	,,	315
Burnt stone slabs	S. ft.	280
Burnt brick in mud (superstructure)	C. ft.	1,513
Burnt stone pillars	,,	38
Do Sq. pillar	Each	1
Honne wood work with oiling, etc., complete ...	C. ft.	66·96
Roofing with Mangalore tiles and teak reepers, etc., complete...	Sq.	13·61
Ridging with Mangalore tiles	R. ft.	62
Zinc sheets for valleys	S. ft.	96
Teakwood eave boards	R. ft.	160
Coping over compound (brick)	,,	44
Teakwood pannelled doors with iron clamps, etc. ...	S. ft.	82
Do windows with shutters, inside glazed shutters and iron bars clamp, etc., complete.	,,	61
Do windows with clamps and iron bars of shutters ...	,,	42
Do battened doors with iron clamps ...	,,	89
Painting to doors and windows	Sq.	3·27
Wood oiling	,,	2·55
Flooring with Mangalore tiles over 3" concrete ...	,,	3·06
Do Cuddapah slabs with concrete bed ...	,,	2·49
Plastering with mortar	,,	43·88
Chunam pointing basement	,,	1·54
Cup boards and pegs wherever necessary ...	L. S.	
White and Colour washing apart plastering with two coats ...	Sq.	43·88
Constructing combined chimney to both kitchen ...	L. S.	
Do seats in latrine	,,	
Clearing silt and levelling ground	,,	
Tarring to wood work	,,	
Pestle and mortar	,,	
Sinking a draw well with pulley close to compound parapet, etc.	,,	
Constructing V-shaped drain	,,	
Gravelling compound	,,	

Items of work.	*Per.*	*Quantity.*
Quarters for the Midwife at Bagepalli.		
Earthwork excavation and filling basement	C. yd.	22
Stone in mud filling foundation	C. ft.	642
Stone in chunam basement	„	175
Burnt brick in mud (superstructure)	„	883
Chunam plastering	Sq.	26·14
Chunam pointing	„	1·36
White and colourwashing	„	26·14
Brick in chunam coping, complete	R. ft.	50
Flooring with Cuddapah slabs over 3″ concrete bed	Sq.	3·48
Brick in chunam cheeks of doors, ventilators, windows and top of walls.	C. ft.	305
Burnt stone slabs, dressed	S. ft.	187
Teakwood battened doors with iron clamps, complete	„	152
Do windows with iron bars clamps, etc., complete, one on either side.	„	41
Expanded metal ventilators with iron clamps, etc., one on either side.	„	36
Painting doors and windows	Sq.	4·64
Tarring wood work	L. S.	
Roofing with 1st class Mangalore tiles with teak reepers 2″×1″	Sq.	8·28
Mangalore ridge tiles set in mortar	R. ft.	27
Teakwood eave boards, plain	„	48
V-shaped and lead of drains from provy	L. S.	
Cut stone pillars with vase and caps, complete	Each	3
Binding wall	R. ft.	50
Honne wood work with oiling	C. ft.	48·32
Constructing a masonry chimney to kitchen with partition wall	L. S.	
Pestal and mortar in kitchen	„	
Cup boards with pegs to support	„	
Constructing seats in latrine	„	
Stone flagging cement pointing tarring 3′ high and drainage pipes.	„	
Clearing site and levelling ground	„	
Flooring with gravel	„	

Dated Camp Srinivaspur, 10th August 1912.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 24th August 1912, for constructing a new Girls' School at Kolar. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1913.

2. The plans, detailed estimate, specifications and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees three hundred (Rs. 300) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a new Girls' School at Kolar," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items of work.	*Per.*	*Quantity.*
Earthwork excavation and filling basement...	C. yd.	245
Concrete in chunam	C. ft.	4,948
Burnt stone in chunam	,,	2,186
Burnt brick in chunam with scaffolding	,,	8,913
Do arch work	,,	581
Burnt stone slabs, dressed	S. ft.	789
Chunam pointing	Sqr.	3·76
Chunam plastering	,,	134·47
White and color washing	,,	134·47
Burnt stone pillars with caps and base with nice dressing ...	Each	4
Teakwood doors pannelled with hinges, bolts and clamps, etc., complete	Sq. ft.	327
Teakwood pannelled windows with glazed shutters inside and pannelled shutters outside with iron bars, clamps, hinges and bolts, etc., complete	,,	480
Teakwood fanlights over windows with glazed shutters, etc., complete	,,	113
Teakwood flat ventilators with iron bars, clamps, etc., complete	,,	72
Teakwood circular do do ...	Each	2
Teakwood finials with scilicate painting	,,	4
Do at eaves, small	,,	8
Teakwood wrought and put up with wood oiling	C. ft.	344·10
Roofing with first class Mangalore tiles with teak reepers, etc., complete	Sqr.	48·22
Cuddapah slab flooring with 3″ concrete bedding and cement pointing complete	,,	18·31
Silicate pointing	,,	26·42
Ridge tiles set in mortar	Rft.	242
Zinc sheets	Sq. ft.	174
Teakwood eave boards, ornamental	R. ft.	474
Brick masonry binding wall with plastering	,,	82
Black board with shell line	Each	10
Teakwood pegs with painting	,,	82
Date stone with chiselling, numbering and painting ...	,,	1
Constructing a drain with box drain to lead off and forming roads in court yard in front and gravelling around the building	Lump sum	
Fixing flat iron bars at ends of eaves	C. W. T.	6
Iron clips fixing, etc.	Each	90
Levelling ground and clearing site	Lump sum	
Constructing a latrine with urinel	Lump sum	
Flooring with concrete and plastering with chunam over it ...	Sqr.	5·87

Note.—The materials, *viz.*, stones, bricks, tiles, Cuddapah slabs already collected should be accepted at the rates fixed by the Executive Engineer.

V. AIYASWAMI IYER,
Executive Engineer.

HASSAN DIVISION.

Notification dated 9th August 1912.

There is a road slip in the 8—149th mile of the Bangalore-Mangalore road near Marnahalli village. The public are hereby informed that a temporary road is opened to the east of the Travellers' Bungalow which should be used somewhat cautiously.

V. R. NIJAGAL,
Executive Engineer.

KADUR DIVISION.

Notice dated 24th July 1912.

The attention of the public is invited to the notification published in the *Mysore Gazette*, dated 1st August 1912, calling for tenders for opening out a feeder from Nagannan Anikat to Tarikere Valley and enlarging the Ramanaikankere tank of Tarikere Taluk, Kadur District.

Notice dated 24th July 1912.

The attention of the public is invited to the notification published in the *Mysore Gazette*, dated 1st August 1912, calling for tenders for Improving the Chik Patnagiri Anikat and Channel, Kadur Taluk, Kadur District.

R. S. NAVARATNA,
Executive Engineer.